

# **ORIENTAL BANK OF COMMERCE**

TENDER DOCUMENT

FOR

RENOVAION WORK BRANCH (MANAGER CABIN ONLY) & ATM

AT

**SECTOR-14, FARIDABAD.**

**Issued To:** .....

## **ARCHITECTS:**

**M/s VASTU SADAN PVT. LTD.**

122 A /12, G.F., GAUTAM NAGAR, NEW DELHI – 110049.

TEL. NO. - 011- 41643626, FAX. NO. – 011-41643426

**SECTION – I****INVITATION TO TENDERS**

- 1.0 Sealed tenders on item rate bases are invited from Bank's empanelled contractors in the prescribed form by the **Regional Head, Oriental Bank Of Commerce, R O, Gurgaon** for **Interior Furnishing Work branch & ATM at Sector-14 Faridabad Branch, Haryana.**

<b>Tender No.</b>	<b>Name of Work</b>	<b>Earnest Money</b>	<b>Time of Completion</b>
<b>OBC /Sec-14/FUR</b>	<b>Interior Furnishing Work branch (Manager Cabin only) &amp; ATM at Sec-14, Faridabad, Haryana.</b>	<b>2600</b> /- in the form of DD	<b>30 Days</b>

- 1.1 The work as detailed in this tender shall be executed and completed in all respect with in a period of **30 Days** from the date of written order to commence the work in accordance with the tender documents, Instruction to tenderers, Technical specification, Schedule of Quantities, Condition of contract, Schedules and drawings, to the satisfaction of Architect / Employer.
- 1.2 The Tenderer(s) are required to deposit **Rs. 2600/-** as Earnest Money along with the tender document in the form of crossed Demand Draft only payable at Gurgaon in favour of Chief Manager, Oriental Bank Of Commerce, Gurgaon.
- The Earnest Money will be refunded without any interest to the unsuccessful tenderers after a decision is taken regarding award of contract.
- Tenders, filled in the prescribed form in sealed covers and super scribed with the name of work, Tender No. **OBC/ SEC-14/ FUR** must be submitted to the **Regional Head, Oriental Bank Of Commerce, Regional Office, Plot No.-80, 4<sup>th</sup> Floor, Institutional Area, Sector-44, Gurgaon** not later than **2.00 P.M. on 04/06/2015**. Tenders will be opened on the same day at **3.00 P.M.** in the presence of tenderers or their representatives.
- 1.3 Tender documents can be downloaded from Bank's website / can be obtained on working day from the office of the **Oriental Bank of Commerce, Regional Office, Plot no 80, IVth Floor, Sector – 44, Gurgaon** on payment of tender cost (non-refundable) of **Rs. 500/- draft in favour of Oriental Bank of Commerce**. The drawings are enclosed along with set of specifications.
- 1.4 Rate must be quoted for complete work at site inclusive of all costs, taxes and charges, etc. All taxes and duties including sales Tax or works contract, E.S.I. charges etc. as applicable at **HARYANA**, central or state sales Tax, octroi, Royalties etc. on works and materials required for use in the execution of this project shall be entirely borne and payable by the contractor and the Employer will not entertain any claim whatsoever in this respect.
- 1.5 The tenders shall remain valid for acceptance by the Employer, for a period of 3 month from the date of opening of tender.
- 1.6 Total Security Deposit shall comprise of :
- Earnest Money Deposit
  - Initial Security Deposit
  - Retention Money
- 1.7 Initial Security Deposit
- 1.7.1 The amount of Initial Security Deposit shall be 3% of the accepted value including earnest money. Initial Security Deposit shall be refunded without any interest to the contractor after the issue of certificate of virtual completion.

1.7.2 The balance amount of Initial Security Deposit is to be paid by the contractor to the Employer within 14 (Fourteen) days of intimation to him or the acceptance of the tender in the form of Demand Draft.

#### 1.8 Retention Money

1.8.1 The retention percentage (i.e. deduction from interim bill) shall be 8% of the gross value of each interim bill.

1.8.2 The maximum amount of retention money shall be the balance amount of the total security deposit.

1.8.3 50% of the retention amount is refunded to the contractor subject to the following:-

- (1) Issue of virtual completion certificate by the Architect / Premises department.
- (2) Contractor should remove his material, equipments, labour force, temporary sheds / stores etc. from the site.

The remaining 50% of the retention money may be refunded 14 ( Fourteen ) days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to all defects in accordance with the conditions of the contract.

1.9 Earnest money of the successful tender will be liable to be forfeited in the event of refusal or delay on his part in deposit initial security deposit and signing the agreement within 7 (seven) days , of the issue of letter of award of the work.

1.10 Tender documents duly filled and signed by the tenderer shall be submitted for the work.

1.11. The Oriental Bank Of Commerce and their approved architect, do not bind itself to accept the lowest or any tender, or to assign any reason thereof and also reserves the right of accepting the whole or part of the tender and the tender shall in such an event be bound to perform the contract at the same rates quoted in the tender for the various items of the work.

1.12. Canvassing in any form in connection with the tender is strictly prohibited and the tenders submitted by the contractors who resort to canvassing from shall be liable for rejection.

1.13. The tendering firms, in case the tender is a partnership firms, shall submit the tender signed by all the partners. In the event of absence of any partner , it must be signed on his behalf by a person holding power of attorney authorizing him to do so and such power of attorney be attached along with the tender .

### APENDIX SHOWING IMPORTANT SCHEDULES

- |     |  |   |  |
|-----|--|---|--|
| 1.  | SIGNING THE AGREEMENT                                  | : | Within 3 <sup>rd</sup> Days of the issue of letter of intend / order.  |
| 2.  | DATE OF COMMENCEMENT OF WORK                           | : | Within 3 <sup>rd</sup> Days of issue of letter of intend / order or the day on which the contractor is given the site whichever is latter. |
| 3.  | PERIOD OF COMPLECTION                                  | : | <b>30 Days</b> from the tender date of commencement of work.   |
| 4.  | LIQUIDATED DAMAGES                                     | : | 1% of contract amount per week of delay subject to the max. of 10% of the accepted contracted sum .  |
| 5.  | PERIOD AND VALUE OF RUNNING / ON ACCOUNT BILL          | : | 75% of amount within 7 <sup>th</sup> days after date of receipt of architect certificate and balance within 21 days.                       |
| 6.  | INITIAL SECURITY DEPOSIT                               | : | 3% of the accepted value of the tender including of the Earnest Money.   |
| 7.  | REFUND OF INITIAL SECURITY DEPOSIT AND RETENTION MONEY | : | (a) <u>INITIAL SECURITY DEPOSIT</u><br>To be released with 14 days after the issue of certificate of virtual completion.                   |
|     |  | : | (b) <u>RETENTION MONEY</u><br>As clause 1.8.3  |
| 8.  | TOTAL SECURITY DEPOSIT                                 | : | As per clause No. 1.7  |
| 9.  | INCOME TAX DEDUCTION                                   | : | As prevailing rate from each bill.   |
| 10. | DEFECTS LIABLITY PERIOD                                | : | 12Months after completion of work.   |
| 11. | PERIOD OF FINAL MEASUREMENT                            | : | 2 Weeks after virtual completion of work.  |

**SECTION – 2**  
**INSTRUCTION TO TENDERERS.**

**INSTRUCTION TO TENDERERS.**

2.1 The tenderer shall examine carefully all the tender documents consisting of –

- Invitation to Tenderers.
- Instruction to Tenderers.
- Form of Agreement.
- General Conditions of Contract.
- Schedule of Quantities.

These shall form part of the Agreement.

The tender is advised to visit and inspect the site at his own cost and responsibility and to secure all necessary information which may be required for completing the tender. Ignorance of site conditions cannot be an excuse for non-performance of the contract. All costs, charges and expenses that may be incurred by the tenderer in connection with the preparation of his tender shall be borne by him and the employer / architect does not accept any liability whatsoever in this regard.

- 2.2 Time is the essence of the contract and the tenderers are required to complete the work in all respects within the stipulated time of completion and handover the same, complete in all respects to the satisfaction of the architect.
- 2.3 The tender should contain not only the rates but also the value of each item of work entered in the prescribed column of the B.O.Q. and all the items should be totaled up in order to show the aggregate value of the entire tender. The rates quoted by the tenderers should be expressed accurately both in words and figures so that there is no discrepancy. All corrections in the tender shall be duly attested by initials of the tenderer, corrections, if not attested may entail rejection of tender. The rates quoted by the tenderers in word in item rate tender will be the basis (and not the amounts in case of discrepancies) in finalizing the tender.
- 2.4 It shall be clearly understood that the rates quoted in the tender are to be, for complete work at site, as per instructions to Tenderers, conditions of contract, specifications and drawings, addenda referred to therein and also for all such works as are necessary for the proper completion of the contract, although specifications thereof may not have been made in the specifications or drawings or tender documents. The rates shall be firm and shall not be subject to cost escalation on account of labour, material and labour conditions or any other reason whatsoever.
- 2.5 The tenderers shall use only the form issued with this tender to fill up the rates.
- 2.6 Every page of the tender shall be signed on the left hand side bottom corner and any tender not so complied with is liable to be treated as defective & liable to be rejected.
- 2.7 In the event of a tender being selected for acceptance. The Oriental Bank Of Commerce will inform the tenderer for the specification and other documents for the acceptance with tender. The successful tenderer shall also deposit the required amount of the security money within the prescribed time and if the tenderer fails to deposit the required amount of the security money within the prescribed period, Oriental Bank of Commerce may reject the tender.
- 2.8 The successful tenderer will be notified about the acceptance of his tender by the Employer and he will have to deposit balance amount initial security and executed

agreement within 7 (Seven) days thereof, failing which his tender would be liable to rejection with forfeiture of the Earnest Money.

- 2.9 The tender shall fill up the complete form of article of agreement before submission of tender. Failure to comply may entail rejection of the tender.
- 2.10 The contractor will be governed by the Indian contract act, Indian sale of good act and all other relevant laws. All payments due to the contractor under the contract will be made in Indian rupee currency.
- 2.11 The rate quoted shall be for complete work at site and should be inclusive of incidentals necessary for carrying out the work. The rates shall be inclusive of sales tax if applicable at **HARYANA** for work contract, central or state sales tax, octroi duty, royalty, ESI or any other tax or duty levied by any government or public bodies. The rate shall be firm and shall not be subject to cost escalation of labour, material and exchange variations, labour conditions and other conditions whatsoever.
- 2.12 A schedule of approximate quantities for various items accompanies this tender. It shall be clearly understood that neither the architect nor the employer will accept any responsibility for the correctness or completeness of this schedule in respect of item and quantities and this schedule is liable to alternations by omission, deduction or addition at the discretion of the employer in consultation with the architect without violating the items of the contract.
- 2.13 The contractor must produce latest income tax clearance certificate along with this tender.
- 2.14 Form of 'Tender of works' contained in section -3 shall be completed along with submission of tender. In case of failure to do so the tender is liable to rejection.
- 2.15 The employer does not bind it self to accept the lowest or any tender or to assign any reason thereof and also reserves the right of accepting the whole or part of the tender. The part acceptance will not violate the terms and conditions of the contract and will execute the work at the specified rates without any extra charges or compensation.
- 2.16 Income tax deductions will be made as per the prevailing rates from the contractor's on account bills.
- 2.17 No mobilization advance or secured advance is to be allowed to the contractor.
- 2.18 Power and water connection if required is to be arranged by the contractor. Cost shall be paid by the employer as per actual billing.

### SECTION - 3

---

#### FORWARDING LETTER

---

FROM:

---

---

---

---

To:

---

---

---

---

Ref.:

---

Dear Sir,

1. With reference to the tender invited by you, I/ we hereby offer to perform, provide, execute and complete the works in conformity with conditions of contract, drawings and specifications for the respective items of schedule of quantities attached hereto.
2. I/ we have satisfied myself / ourselves as to the location and prevailing conditionings of the site, and have read carefully the articles of agreement, condition of contract, specification, general and special conditions, technical specifications etc, and I/We understand that the works are to be completed within **30 Days** from the date of commencement and fully understand that the time will be the essence of the contract.
3. I/We enclosed a demand draft for **Rs. 2600/-** drawn on Oriental Bank of Commerce payable at **Gurgaon** in favour of the **Oriental Bank of Commerce** as earnest money and fully understand that this amount will not bear any interest.
4. I/We agree to keep the offer for 3 months from the date of opening the tender.
5. Should this tender be accepted in whole or in part, I/We hereby agree to abide by and fulfill and the terms and conditions annexed hereto. I/We fail to commence the work specified in tender documents , I/We agree that my / our earnest money shall stand forfeited absolutely to the Employer otherwise the said Earnest money shall be retained by the Employer towards security deposit (retention money) .
6. All the terms and conditions contained in the notice Inviting Tenders, Conditions of Tenders, General conditions of contract, specifications for execution of the work, additional conditions and the agreement etc. constituting the tender documents have

been fully read by me/us and explained to me/us and I/We hereby accept the same and sign hereunder in token of their acceptance.

7. We are further enclosing herewith the following documents :-

- i) Partnership Deed. Article of Association and power of Attorney. We agree that no change will be made in these documents without prior approval of the Oriental Bank Of Commerce
- ii) Tender documents duly signed along with detailed program and targets of completion of each items work.
- iii) Detail of deployment of manpower, machinery, plant and equipment.
- iv) Demand Draft No. \_\_\_\_\_ Date \_\_\_\_\_ Drawn \_\_\_\_\_  
\_\_\_\_\_

Name of the partners / Directors  
of the firm 1)

2)

Date: \_\_\_\_\_

Witness: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Occupation: \_\_\_\_\_

Yours faithfully,

Name & Sign. of Tenders (s) office  
Stamp and seal of the Tenders (s).

## **SECTION – 4**

### **AGREEMENT**

## AGREEMENT

This agreement made at \_\_\_\_\_ day of \_\_\_\_\_, between the **Oriental Bank Of Commerce**, having its registered office at **Regional Office, Plot No.-80, 4<sup>th</sup> Floor, Institutional Area, Sector-44, Gurgaon** (herein after called the Employer which expression shall include their heirs, executors, administrators and assignees) of the one part and M/S \_\_\_\_\_ (herein after called the 'Contractor') of the other part. Whereas the employer is desirous that work should be executed as per drawings and specifications describing the work to be done, to be prepared by their approved Architects and WHEREAS the said drawings, the specifications and the price schedule of quantities have signed by or on behalf of the parties hereto and WHEREAS the contractor has agreed to execute upon and subject to the conditions set forth herein and the said priced schedule of quantities at the respective rates mentioned in the priced schedule of quantities, which as part of the tender document.

And WHEREAS the contractor has deposited **Rs. 2600/-** as the Earnest Money with the Employer, which shall become part of security deposit to be until the expiry of the Defect liability period for the due observance of the contract.

### NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

1. In consideration of the said contract, payments to be made to the said conditions execute and complete the works shown upon the said Drawings and such further detailed drawings as may be furnished to him by the said Architects and described in the specifications and the said priced schedule of quantities.
2. The employer shall pay the contractor such sums as shall become payable hereunder at the times and in the manner specified in the said conditions.
3. The said contract comprised the building above mentioned and all subsidiary works connect there within the same site as may be ordered to be done from time to time by the said Architects even, through such works may not be shown on the Drawings or described in the said specification or the priced schedule of quantities.
4. The Employer through Architect reserves to himself the right of altering the drawing and nature of the work and adding to or omitting any items of works, check of measurement, payment certificate, variation arising in view of change of scope of work and approval of rates of extra substituted items. The decision of the Employer shall be final and binding in this regard.
5. The Employer in consultation with the Architect reserves the right to exercise control on quality of work, check of measurement, payment certificate, variation arising, in view of change of scope of work and approval of rates of extra submitted items. The decision of the Employer shall be final and binding this regard balance retention money being deducted from my /our bills in accordance with the conditions of contract.
6. The following documents shall be deemed to form and constructed as part of this agreement along with the amendments, negotiated and confirmed in various subsequent latter exchanged as mentioned hereinafter and parties hereto will respectively abide by and submit themselves to the conditions and stipulations and perform the agreement on their parts respectively in such conditions contained.
  - i) Invitation to Tender.
  - ii) Instruction to Tenderers.
  - iii) General Conditions of the contract.

- iv) Schedule of Quantities.
  - v) Employer letter date \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_ to the contractors awarding the contract.
  - vi) Contractors letter date \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_ to the Employer in acceptance of the award of contract.
7. All disputes arising out of or in any way connected with the agreement shall be deemed to have arisen at Haryana only, the court in Haryana shall have jurisdiction to determine the same.
8. The several parts of this contract have been read to us and fully understood by us.

Witness our hand this..... day of .....2015

SIGNED BY THE SAID .....  
(EMPLOYED)

IN THE PRESENCE OF .....

ADDRESS .....

SIGNED BY THE SAID .....  
(CONTRACTOR)

IN THE PRESENCE OF .....

ADDRESS .....

## **SECTION – 5**

### **GENERAL CONDITION OF CONTRACT**

Except where provided for in the description of the individual items in the schedule of quantities and in the specifications and conditions laid down hereinafter and in the drawing. The work shall be carried out as per standard specifications and under the direction of employer / Architect.

#### **1. INTERPRETATION**

In construing these conditions, the specifications, the schedule of quantities, tender and agreement, the following words shall have meaning herein assigned to them except when the subject or context otherwise required.

- i) Employer: The term employer shall mean Oriental Bank Of Commerce having their head office at Plot No. 5, Sec-32, Gurgaon, and any of its employees representative authorized on their behalf.
- ii) Architect: The term architect shall mean the approved architects of Oriental Bank of Commerce or in the event of his / their ceasing to be the architect for the purpose of this contract such other person/s as the employer shall nominate for the purpose.
- iii) Contractor: The term contractor shall mean Company, firm or the party to whom the Contract is awarded and shall include his / their legal representative(s) or successor(s).
- iv) Site: Shall mean the places or buildings envisaged by the employer where the work is to be executed or carried out.
- v) Site Engineer: The bank may appoint the site engineer. The bank may also determine the number of site engineer and the supporting staff at site office to assist them and also whether the site engineer shall be temporary or permanent. As far as possible, the site engineer should assume charge of his post before the contractor reports on site of work. Where more than one site engineer is appointed, one of them shall be designated as senior site engineer by the premises department and the other site engineer shall be reporting to the senior site engineer.
- vi) Drawings: The work is to be carried out in accordance with drawings, specifications, the schedule of quantities and any further drawings which may be supplied or any other instruction, which may be given by the employer during the execution of work.

All drawings relating to work given to the contractor together with a copy of schedule of quantities are to be kept at site and the employer / Architect shall be given access to such drawings or schedule of quantities whenever necessary.

In case any detailed drawings and necessary contractor shall prepare such detailed drawing and / or dimensional sketches therefore and have it confirmed by the employer / Architect prior to taking up such works.

The contractor shall ask in writing for any clarification on matters occurring anywhere in drawings, specifications and schedule of quantities or to additional instructions at least 10 days ahead from the time when it is required for implementation so that the employer may be able to decision thereon.

- vii) "The Works" shall mean the work or works to be executed or done under this contract.
- viii) "Act of Insolvency" shall mean any act as such as defined by the presidency town's insolvency act or provisional insolvency act or any amending statues.
- ix) "The schedule of quantities" shall mean the schedule of quantities as specified and forming part of this tender.

- x) "Priced schedule of quantities" shall mean the schedule of quantities duly priced with the accepted quoted rates of the contractor.

## 2. SCOPE

The work consists of **Renovation work branch (Manager Cabin only) & ATM at Sector-14, Faridabad, Haryana** in accordance with the "drawings" and "Schedule of quantities". It includes furnishing all material, labour, tools and equipments and management necessary for the incidental to the construction and completion of the work. All works, during its progress and upon completion, shall conform to the lines, elevations and grades as show on the drawings furnished by the employer / architects. Should any detail essential for the efficient completion of the work to be omitted from the drawings and specifications, it shall be responsibility of the contractor to inform the employer / architects and to furnish and install such detail with employer's / architect's concurrence, so that ,upon completion of the proposed work , the same will be acceptable and ready for use.

Employer/ Architect may in their absolute discretion issue further drawings and / or written instructions, details, directions and explanations, which are hereafter collectively referred to as "The Employer's / Architect's instructions in regard to:

- a) The variation and modification of the design quality or quantity of works or the addition or omission or substitution of any work.
- b) Any discrepancy in the drawings or between the schedule of quantities and / or drawings and / or specification.
- c) The removal from the site of any defective material brought thereon by the contractor and the substitution of any other material thereof.
- d) The demolition removal and / or re-execution of any work executed by the contractor's.
- e) The dismissal from the work of any persons employed thereupon
- f) The opening up for inspection of any work covered up.
- g) The rectification and making good of any defects under clauses hereinafter mentioned and those arising during maintenance period (retention period)

The Contractor shall forthwith comply and duly execute any work comprised in such employer / Architect's Instructions provided always that verbal instructions, directions and explanations given to the contractor or his representative upon the works by the employer / Architects shall, if involving a variation, be confirmed in writing to the Contractor within seven days. No work, for which rates are not specifically mentioned in the priced schedule of quantities, shall be taken up without written permission of the employer / architect. Rates of items not mentioned in the priced schedule of quantities shall be fixed by the employer in consultation with the architects as provided in clause 'variation'.

Regarding all factory made products for which ISI marked products are available, only products bearing ISI marking shall be used in the work.

## 3. TENDERER SHALL VISIT THE SITE

Intending tenderer shall visit the site and make him thoroughly acquainted with the local site condition. Nature and requirement of the works, facilities of transport condition effective labour and materials, access and storage for material and removal of rubbish. The tender shall provide in their tender for cost of carriage, height and other charges as also for any special difficulties and including police restriction for transport etc. for proper execution of work as indicated in the drawings. The successful tenderer will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site condition which existed before the commencement of the work or which in the opinion of the employer / architects might be deemed to have reasonably been inferred to be existing before commencement of work.

#### 4. TENDERS

The entire set of tender paper issued to the tenderer should be submitted fully priced also signed on the last page together with initials on every page. Initial / signature will indicate the acceptance of the tender paper by the tenderer.

The schedule of quantities shall be filled in as follows:-

- i) The rate column to be legibly filled in ink in both English figures and words.
- ii) Amount column to be filled in for each item and the amount for each subhead as detailed in the "Schedule of Quantities".
- iii) All corrections to be initialed.
- iv) The rate column for alternative items shall be filled up.
- v) The "Amount" column for alternative items of which the quantities are not mentioned shall not be filled up.
- vi) In case of any error / omissions in the quoted rates, the rates given in the tender marked "Original" shall be taken as correct rates.

No modifications, writing or corrections can be made in the tender papers by the tenderer but may at his option offer his comments or modifications in a separate sheet of paper attached to the original tender papers.

The employer reserved the right to reject the lowest or any tender and also to discharge any or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should not that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self-supporting. It called upon by the employer / architects detailed analysis of any or all the rates shall be submitted. The employer / architect shall not be bound to recognize the contractor's analysis.

The work will be paid for as "measured work" on the base of actual work done and not as "lump sum" contract.

All items of work described in schedule of quantities are to be deemed and paid as complete work in all respects and details including preparatory and finishing work involved, directly related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charge will be allowed in this connection. In the case of lump sum charge in the tender in respect of any item of works the payments of such items of work will be made for the actual work done on the basis of lump sum charges as assessed by the employer / architect.

The employer has power to add to, omit from any work as shown in drawings, or described in specifications or included in schedule of quantities and intimate the same in writing, but no addition, omission or variation shall be made by the contractor without authorization from the employer. No variation shall vitiate the contract.

The tenderer shall note that his tender shall remain open for consideration for a period of 3 months from the date of opening of the tender.

#### 5. AGREEMENT

The successful contractor required to sign agreement as may be drawn up to suit local conditions and shall pay for all stamp and legal expenses, incidental thereto.

#### 6. GOVERNMENT AND LOCAL RULES

The contractor shall confirm to the provisions of all local bye-laws and acts relating to work and to the regulations etc. of the govt. and the local authorities and of any company with whose system the structure is proposed to be connected. The contractor shall give all notices required by said act, rules, regulations and bye-laws etc. and pay all fees payable to

such authority/ authorities for execution of work involved. The cost if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses, fees for footpath encroachment and restoration etc. and shall indemnify the employer against such liabilities and shall defend all actions arising from such claim or liabilities.

## 7. TAXES AND DUTIES

The tenderer must include in their tender prices quoted for all duties royalties, excise and sales tax or any other taxes or local charges if applicable. No extra claim on this account will in any case be entertained.

## 8. PROVISIONAL SUM (P.S.)

All provisional sums described in the schedule of quantities as P.S. shall be exclusively allotted to the purchase of material and not for any handling and fixing to be done by the contractor. Such cost of handling and fixing with profit (including transport charges if required) shall be separately included in the contract price as described in the schedule of quantities. The disposal of the amount cover under this head will be absolutely at the discretion of the employer. Contractor is to make payments for these materials to the supplier on certificate or order issued by the employer / architect and release them through his bills from the employer.

## 9. QUANTITIES OR WORK TO BE EXECUTED

The quantities shown in the schedule of quantities are intended to cover the entire new structure indicated in the drawings but the employers reserves the right to execute only a part or the whole or any excess thereof without assigning any reason therefore.

## 10. OTHER PERSONS ENGAGED BY THE EMPLOYER

The employers reserves the right to execute any part of the work in this contract or any work which is not included in this contract, by other agency or persons and contractor shall allow all reasonable facilities and use of his scaffolding for the execution of such work. The main contractor shall extend all co-operations in this regard.

## 11. EARNEST MONEY AND SECURITY DEPOSIT

The tenderer will have to deposit an amount of **Rs. 2600/** - in the form of bank draft drawn in favour of **ORIENTAL BANK OF COMMERCE** at the time of submission of tender as an earnest money. The employer is not liable to pay any interest on the earnest money. The earnest money of the unsuccessful tenderers will be refunded without any interest soon after the decision to award the work is taken or after the expiry of the validity period of the tender.

The successful tenderer to whom the contract is awarded will have to deposit an initial security deposit a further sum to make up 3% of the value of the accepted tender including the earnest money. The initial security deposit will have to make within 14 days from the date of acceptance of tender failing which the employer at his discretion may revoke the letter of acceptance and forfeit the earnest money deposit furnished along with the tender. The initial security deposit will be invested by the employer in a fixed deposit account for the duration of the contract period. It shall be refunded to the contractor along with accrued interest within fourteen days after the issue of certificate of virtual completion.

Apart from the initial security deposit made as above, retention money shall be deducted from progressive running bill @ 8% of the gross value of each running bill until the total security deposit i.e. the initial security deposit plus the retention money equals:

- a) 10% on the first one lakh rupees of the estimated cost of work.
- b) 7.5% on the next one lakh rupees of the estimated cost of work.
- c) 6% on the remaining amount of the estimated cost of work, subject to a ceiling on total security deposit rupees ten lakhs (Rs. 10, 00, 000)

The retention amount will be refunded to the contractor 14 days after the end of defect liability period provided he has satisfactorily carried out all the work and attended to all defects in accordance with the condition of the contract. No interest is allowed on retention money.

## **12. CONTRACTOR TO PROVIDE EVERYTHING NECESSARY**

The contractor shall provide everything necessary for the proper execution of works according to the intent and meaning of the drawings, specifications and Schedule of Quantities taken together whether the same may or may not be particularly shown or described therein, provided that the same can reasonably be inferred there from and if the Contractor finds any discrepancy in the drawings or between the drawings, general conditions, specifications and Schedule of Quantities, he shall immediately refer the same in writing to the employer / Architect, whose decisions shall be final and binding. The contractor shall provide himself for ground and fresh water for carrying out of the works at his own cost. The employer shall on no account be responsible for the expenses incurred by the contractor for hired ground or fresh water obtained from elsewhere.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of work within the contemplation of the contract, and beyond the unit price no extra payment will be allowed for incidental or contingent work, labour and / or material inclusive of all taxes and duties whatsoever except for specific items. If any, stipulated in the tender documents.

## **13. TIME OF COMPLETION, EXTENSION OF THE PROGRESS CHART**

1. Time of completion: The entire work is to be completed in all respects within the stipulated period. The work shall be deemed to be commenced within the fourteen days from the date of acceptance letter or date of handing over of site, whichever is earlier. Time is the essence of the contract and shall be strictly observed by the contractor.

The work shall not be considered as complete until the employer / architects have certified in writing that his has been completed and the defect liability period shall commence from the date of such certificates.

2. Progress of Work: During the period of construction the contractor shall maintain proportionate progress on the basis of a program chart submitted by the contractor immediately before commencement of work and agreed to by the employer / architects. Contractor should also include planning for procurement of scarce material well in advance and reflect the same in the program chart so that there is no delay in completion of the project.

## **14. LIQUIDATED DAMAGES**

Should the work not be completed to the satisfaction of the employer / architect within the stipulated period, the contractor shall be bound to pay to the employer a sum calculated as given below by way of liquidated damages and not as penalty during which the work remains uncompleted or unfurnished after the expiry of the completion date.

- |  |   |
|--|---|
| a) For contracts having time for<br>4 month or less  | 1% of the estimated amount shown in Completion the tender per week subject to a ceiling of 10% of the accepted contracted sum |
| b) For contracts having time for<br>Completion exceeding 6 month<br>but not exceeding 2 years<br>(24 months) | 0.5% of the estimated amount shown in the tender per week subject to a ceiling of 7.5% of the accepted contracted sum.        |
| c) For contracts having time for<br>Completion in excess of 2 years  | 0.25 % of the estimated amount shown in the tender per week subject to a ceiling of 5% of the accepted contracted sum.        |

**15. ACCESS**

Any authorized representative of the employer shall at all reasonable times have free access to the works and/or to the workshops, factories or other places where item/items of work are being prepared or manufactured for the contract and also to any place where the materials are lying or from which they are being obtained. The Contractor shall give every facility to the Architect, Owner and their representative for the inspection and examination and test of the materials and workmanship. Except the representative of employer no person, shall be allowed at any time without permission of the employer.

**16. MATERIAL, WORKMANSHIP, SAMPLES, TESTING OF MATERIALS**

All the works specified and provided for in the specification or which may be required to be done in order to perform and complete any part thereof shall be executed in the best and most workman like manner with materials of best and approved quality of the respective kinds in accordance with the particular contained in the implied by the specifications and as represented by the drawings or accordance to such other additional particulars and instruction as from time to time be given by the employer / architect during the execution of the work , and to his entire satisfaction.

If required by the employer / architect the contractor shall have to carry out test on materials and workmanship in approved material testing laboratories or as prescribed by the employer / architect at his own cost to rove that the materials etc. under test confirm to the relevant IS standards or as specified in the specifications. The necessary charges for preparation of mould (in case of concrete cube) transporting, testing etc. shall have to be done by the contractor. No extra payment on this account should in any case be entertained.

All the material (except where otherwise described) store and equipment required for the full performance of the work under the contract must be provided through normal channel and must include charge for import duties, sales tax, octroi and other charges and must be the best of their kind available and the contractor/s must be entirely responsible for the proper and efficient carrying out of the work. The work must be done in the best workman like manner. Samples of all materials to be used must be submitted to the employer / architect when so directed by the engineer / architect.

**17. REMOVAL OF IMPROPER WORK**

The employer shall, during the progress of the works, have power to order in writing from time to time the removal from the works, within such reasonable time/times, as may be specified in the order, of any materials which in the opinion of the employer /architect are not in accordance, with the specifications or instructions, and the substitution of proper materials and proper re-execution of any work, executed with materials or workmanship, not in accordance with the drawings and specifications or instructions. In case contractor refuse to comply with the orders, the employer shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental thereto as certified by the employer / architect shall be borne by the Contractor, or may be deducted from any money due to or may become due to the Contractor. No certificate which may be given by the architect shall relieve the contractor from his liability in respect of unsound work or bad material.

**18. SITE ENGINEER**

The term "Site Engineer" shall mean the person appointed and paid by the Employer superintend the work. The contractor shall afford the Site Engineer every facility and assistance for examining the works and materials and foe checking and measuring work and materials. The Site Engineer shall have no power to revoke, alter, enlarge or relax any requirements of the contractor or to sanction any day work, additions, alterations, deviations or omissions or any extra work whatever, except in so far as such authority may be specially conferred by a written order of the employer.

The Site Engineer shall have power to give notice to the contractor or to his foreman, of non-approval of any work or materials and such work shall be suspended of the use of such materials shall be discontinued until the decision of the Employer is obtained. The Architects, from time to time, will examine the work. Engineer from the premises Department of the Employer and the Site Engineer. But such examination shall not in any way exonerate the contractor from the obligation to remedy any defects, which may be found to exist at any stage of the work or after the same is complete. Subject to the limitation of this clause the contractor shall taken instructions only from the Architects / Employer.

## **19. CONTRACTOR'S EMPLOYERS**

The contractor shall employ technically qualified and competent supervisors for the work who shall be available (by turn) throughout the working hours to receive and comply with instructions of the Employer / Architects. The contractor shall engage at least one experienced Engineer as site-in-charge for execution of the work. The contractor shall employ in connection with the work persons having the appropriate skill or perform their job efficiently.

The contractor shall employ local labourers on the work as far as possible. No labourer below the age of sixteen years and who is not an Indian National shall be employed on the work.

Any labourer supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of the employer or his representative shall be deemed to be a person employed by the contractor.

The contractor shall comply with the provisions of all labour legislation including the requirements of.

- a) Employer's Liability Act.
- b) Workman's Compensation Act.
- c) Contract Labour ( Regulation & Abolition ) Act, 1970 and Central Rules 1971
- d) Apprentices Act 1961
- e) Any other Act or enactment relating thereto and rules framed hereunder from time to time.

The contractor shall keep the Employer saved harmless and indemnified against claims if any of the workmen and an costs and expenses as may be incurred by the Employer in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost the order of requirement of any Health Officer of the State or any local authority or of the Employer regarding the maintenance of proper environmental sanitation of the area where the contractor's labourers are housed or accommodated, for the prevention of small pox. Cholera, plague, typhoid, maintain and keep in good sanitary conditions adequate sanitary accommodation and provide facilities for pure drinking water at all times for the use of men engaged on the works and shall remove and clear away the same in completion of the works. Adequate precautions shall be taken by the contractor to prevent nuisance of any kind on the works or the lands adjoining the same.

The contractor shall arrange to provide first aid treatment to the labourers engaged on the works He shall within 24 hours of the occurrence of any accident at or about the site or in connection with execution of the works, report such accident to the Employer and to the competent authority where such report is required by law.

## **20. DISMISSAL OF WORKMEN :**

The contractor shall on the request of the employer immediately dismiss from the works any person employed thereon who may, in the opinion of the employer, is unsuitable or incompetent or who may misconduct himself, and such person shall not again be employed or allowed on the works without the permission of the employer. The employer shall not enter into correspondence for stating the reasons for dismissal of such workmen. Such

discharge shall not be the basis of any claim for compensation or damages against the employer or any of their officer or employee.

## **21. ASSIGNMENT**

The whole works included in the contract shall be executed by the contractor and the contractor shall not directly or indirectly transfer, assign or underlet the contract or any part share thereof or interest therein, nor shall take a new partner, without the written consent of the employer and no subletting shall relieve the contractor from the full and entire responsibility of the contract or from active superintendence of the works during their progress.

## **22. DAMAGE TO PERSONS AND PROPERTY INSURANCE ETC.**

The contractor shall be responsible for all injury to persons, property or things and for all structural and decorative damage to property which may arise from operation or neglect or default of himself or of any Sub--Contractor or of any of his or a Sub-Contractor's employees, whether such injury or damage may arise from carelessness, accident or any other cause whatever in any way connected with the carrying out of this contract. This clause shall be held to include, interlace any damage to buildings, whether immediately adjacent or otherwise, any damage to roads, streets, footpaths, bridges, or ways as well as damages caused to the buildings and works forming the subject of this contract by rain, wind or other inclemency of the weather. The Contractor shall indemnify the Employer and hold him harmless in respect of all, and any expenses arising from any such injury or damage to persons or property as aforesaid and also in respect of any claim made in respect of injury or damage under any acts of Governments or otherwise, and also in respect of any award of compensation or damages consequent upon such claim.

The Contractor shall reinstate all damages of every sort mentioned in this clause, so as to deliver up the whole of the Contract works complete and perfect in every respect and so as to make good or otherwise satisfy all claims for damage to the property or third parties.

The contractor shall affect the insurance necessary and indemnify the employer entirely from all responsibility in this respect. The insurance must be placed with a company approved by the employer and must be effected jointly in the names of the contractor and the employer and the policy lodged with the latter. The scope of insurance is to include damage or loss to the contract itself till this is made over in a complete state. Insurance is compulsory and must be affected from initial stage. The contractor shall be responsible for anything, which may be excluded from the Insurance Policies above referred to, and also for all other damages to any property arising out of and incidental to the negligent or defective carrying out of this contract.

The employer shall be at liberty and is hereby empowered to deduct the amount of any damages, compensations, costs charges and expenses arising or occurring from or in respect of any such claims or damages from any sums due or to become due to the Contractor.

## **23. INSURANCE**

Unless otherwise instructed the contractor shall insure the work and keep them insured until the virtual completion of the contract against loose or damage by fire and / or earthquake, flood. The insurance must be placed with a company approved by the employer, in the joint names of the employer and the contractor for such amount and for any further sum if called to do so by the employer, the premium of such further sum being allowed to the contractor as an authorized extra.

The contractor shall deposit the policy and receipts for the premiums with the employer within 10 days from the date of signing the Contract. In default of the Contractor insuring as provided above, the employer on his behalf may so insure and may deduct the premiums paid from any money due or which may become due to the contractor. The Contractor shall

as soon as the claim under the policy is settled, or the work reinstated by the In Insurance office, should they elect to do so proceed with all due diligence with the completion of the works in the same manner as though the fire had not occurred and in all respects under the same conditions of contract. The contractor in case, of rebuilding or reinstatement after fire, shall be entitled to such extension of time for completion as the employer may deem fit.

#### **24. ACCOUNTS RECIEPTS AND VOUCHERS**

The contractor shall, upon the request of the employer furnish them with invoices, accounts, receipts and other vouchers that they may required in connection with the work under this contract. If the contractor shall use materials less than what he is required under the contract the value of the difference in the quantity of the material he was required to use and that he actually used shall be deducted from his dues. The decision of the employer shall be final and binding on the contractor as to the amount of the material is required to use for any work in this contract.

#### **25. MEASUREMENT**

Before taking any measurement of any work the site engineer or a subordinate deputed by him shall give reasonable notice to the contractor. If the contractor fails to attend at the measurement after such notice or fails to countersign or to record the difference within a week from the date of measurement in the manner required by the site engineer then in any such event the measurement taken by the site engineer or by the subordinate deputed by him as the case may be is final and binding on the contractor and the contractor shall have no right to dispute the same.

#### **26. PAYMENTS**

The bills of the Contractor's shall be submitted to the Architects which in turn shall duly forward the same certifying the correctness thereof along with all the relevant records to the employer within a week of the receipt of bills and other records from the Architects subject to deduction of applicable taxes, advances, security deposits etc. or such other sums as may be agreed or provided for under the Contract

All the interim payments shall be regarded as payments by way of advance against the final payments for work actually done and completed, and shall not preclude the requiring of bad, unsound, and imperfect or unskilled work to be removed and taken any and reconstructed, or recreated or be considered as an admission of the performance of the contract, or may part thereof in any respect or the accruing of any claim, nor shall it conclude determine or affect in any way the power of the Employer under these conditions or any of them as to the final settlement and adjustment of the accounts or otherwise or in any other way vary or affect the contract .

Final payment: - The final bill shall be accompanied by a certificate of completion from that employer/ Architect. Payments of final bill shall be made after deduction of retention money as specified in clause 11 of these conditions, which same shall be refunded after the completion of the defect liability period after receiving the employer's / architects certificates that the contractor has rectified all defect to the satisfaction of the employer / architect. The acceptance of payment of the final bill the contractor would indicate that he will have no further claim in respect of the work executed.

#### **27. VARIATION / DEVIATION**

The price of all such additional items/ non tendered items will be worked out on the basis of rates quoted for similar items in the contract wherever existing or on engineering rate analysis based on prevalent fair price of labour, material and other components as required. The tender rates shall hold good for any increase or decrease in the tendered quantities up to variations of 25%. For variation beyond  $\pm 25\%$  the rate for the respective items may be reviewed on mutually agreed terms.

**28. SUBSTITUTION**

Should the contractor desire to substitute any material and workmanship, he / they must obtain the approval of the employer / architect in writing for any such substitution well in advance. Material designated in this specification indefinitely by such terms as "Equal" or other approved etc. specific approval of the employer / architect has been obtained in writing.

**29. PREPARATION OF BUILDING WORKS FOR OCCUPATION & USE ON COMPLETION**

The whole of the work will be thoroughly inspected by the contractor and deficiencies and defects put right on completion of such inspection the contractor shall inform the Employer that he has completed the work and it is ready for inspection .

On completion the contractor shall clean windows, and doors including oiling if necessary, of all hardware, inside and outside and every part of the premises. He will leave the entire premises neat and clean and ready for immediate occupation and total satisfaction of the Bank.

**30. CLEARING SITE ON COMPLETION**

On completion of the works the contractor shall clear away and remove from the site construction plant, surplus material, rubbish and temporary works of every kind and leave the whole of the site and the works clean and in a workmanlike condition to the satisfaction of the employer / architect.

**31. DEFECTED AFTER COMPLETION.**

The contractor shall make good at his own cost and to the satisfaction of the Employer all defects, shrinkage, settlements or other faults which may appear within 13 months after completion of the work. In default the Employer may employ and pay other persons to amend and make good such damages , losses and expenses consequent thereon or incidental there to shall be made good and borne by the contractor and such damages , loss and expenses shall recoverable from him by the employer or may be deducted by the employer , in lieu of such amending and making good by the contractor deduct from any money due to the contractor a sum equivalent to the cost of amending such work and in the event of the amount retained being insufficient , recover that balance from the contractor from the amount retained under clause No. 12 together with any expenses the Employer any have incurred in connection therewith.

**32. CONCEALED WORK**

The contractor shall give due notice to the employer / architects whenever any work is to be buried in the earth, concrete or in the bodies of walls or otherwise becoming inaccessible later on, in order that the work may be inspected and correct dimensions taken before such burial, in default whereof the same shall at ht opinion of the employer / architect be either opened up for measurement at the contractor's expenses or no payment may be made for such materials. Should any dispute or differences arise after the execution of any work as to measurements etc. or other matters which cannot be conveniently tested or checked , the notes of the Employer / Architects shall be a accepted as correct and binding on the contractor .

**33. ESCALATION**

The rate quoted shall be firm throughout the tenure of the contract (including extension of time, if any, granted) and will not be subject to any fluctuation due to increase in cost of material, labour, sales tax, octroi etc. unless specially provided in these documents.

The price variation clause being adopted by the RBI may be followed, if such a situation arises on a case basis.

**34. SUSPENSION**

If the Contractor, except on account of any legal restraint upon the employer preventing the continuance of the works, or in the opinion of the employer, shall neglect or fail to proceed with due diligence in the performance of his part of the Contract or if he shall more than once make default, the employer shall have the power to give notice in writing to the Contractor requiring that the works be proceeded within a reasonable manner, and with reasonable dispatch, such notice shall not be unreasonably given and must signify that it purports to be a notice under the provisions of this clause and must specify the acts or defaults on the part of the Contractor upon which it is based.

After such notice shall have been given to the contractor shall not be at liberty to remove the site of works or from any ground continuous thereto any plant and materials to subset from date of such notice being given until the notice shall have been complied with. If the contractor shall fail for 7 (seven) days after such notice has been given to proceed with the works as therein prescribed, the employer may proceed as provided in clause 40 (Termination of contract by employer).

**35. TERMINATION OF CONTRACT BY EMPLOYER**

If the contractor being a company going in to liquidation whether voluntary or compulsory or being a firm shall be dissolved or being an individual shall be adjudicated insolvent or shall make an assignment or a composition for the benefit of the greater part, in number of amount of his creditors or shall enter in to a deed or arrangement with his creditors, or if the Official Assignee in insolvency, or the receiver of the contractor in insolvency, shall repudiate the contract or if a Receiver of the contractor's firm appointed by the court shall be unable, within the fourteen days after notice to him requiring him to do so, to show to the reasonable satisfaction of the employer that he is able to carry out and fulfill the contractor and if so required by the contractor to give reasonable security therefore, or if the contractor shall suffer execution to be issued, or shall suffer any payment under this contract to be attached by or on behalf of and of the creditors of the contractor, or shall assign, charge or encumber this contract or any payment due or which may become due to the contractor, there under, or shall neglect or fail to observe and perform an or any of the acts matters of things by this contract to be observed and performed by the contractor within three clear days after the notice shall have been given to the contractor in manner hereinafter mentioned requiring the contractor to observe or perform the same or shall use improper materials or workmanship in carrying on to the works, or shall in the opinion of the employer not exercise such due diligence and make such due progress as would enable the work to be completed within due time agreed upon, and shall fail to proceed to the satisfaction of the of the employer after three clear days notice requiring the contractor so to do shall have been given to the contractor as hereinafter mentioned, or shall abandon the contract then and in any of the said cases, the employer may not with standing previous waiver determine the contract by notice in writing to the effect as hereinafter mentioned, but without thereby effecting the powers of the employer of the obligations and liabilities of the contractor the whole which shall continue in force as fully as if the contract had not been so determined and as if the works subsequently executed had been executed by or on behalf of the contractor ( without thereby creating trust in favour of contractor) further the employer or his agent or servants, may enter upon and take possession of the work and all plants, tools, scaffolding, shed , machinery, steam and other power, utensils and material lying upon premises or the adjoining lands or roads of sell the same as MS own property or may employ the same by mesa of his own servants and workman in carrying on and completing the work or by employing any other contractor or other persons or person to complete the work, the contractor shall not in any way interrupt or do any act matter of thing to prevent or hinder such other contractors or other persons or person employed from completing and finishing or using the material or plants for the works when the works shall be completed, or as soon thereafter as conveniently may be the employer shall give notice in writing to the contractor to remove MS surplus material and plants, and should the

contractor fail to do so within 14 days after receipt by him the employer may sell the same by public auction and shall give credit to the contractor for the amount to so released. Any expenses or losses incurred by the employer in getting the works carried out by the other contractor shall be adjusted against the amount payable to the contractor by way of selling his tools or plants or due on account of work carried out by the contractor prior to engaging other contractor or against the security deposit.

### **36. ARBITRATION**

In the event of any dispute or difference whatsoever arising between the parties out of or pertaining to any Clause of this Contract including any question relating to meaning and interpretation of this contract or any alleged breach thereof, except those the decisions whereof have been specifically provided in the Contract, the same shall be settled as far as possible by mutual discussions and consultations between the parties.

In case of failure to resolve the difference/dispute in the above manner, the same shall be referred to the sole arbitration of any person appointed by mutual consultation of employer and contractor, who shall be presently unconnected with the organization for which the work is executed.

The Arbitrator shall give a separate award in respect of each dispute or difference referred to him.

The Arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasoned award. The venue of the Arbitrator shall be such place as may be fixed by the arbitrator in the sole discretion.

The fees, if any of the arbitrators shall if required to be paid before the award is made and publishing, be paid half by each of the parties. The cost of the reference and of the award including the fees if any, of the arbitrator who may direct to and by whom and in what manner, such cost or any part thereof shall be paid and may fix or settle and amount of costs to be so paid.

The award of the Arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitrator proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under clause shall be a condition precedent to any right and action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

**LIST OF APPROVED MAKE /VENDORS**

1. <i>G.I. Steel section IS 277-1985 Part I Certified</i>	1. INDIA GYPSUM
2. <i>Glass Reinforced Gypsum Board / tiles IS 2095-1982 certified</i>	2. LAFARGE
3. <i>Clear Float Glass</i>	1. INDIA GYPSUM
4. <i>Flush doors IS : 2202 Certified Part I</i>	2. LAFARGE
	1. MODI
	2. SAINT-GOBIN
	1. GREENLAM
	2. DURO
	3. ARCHIDPLY
	4. JYOTI PLY
	5. EURO
	6. CENTURY
5. a) <i>19mm thk. Block Board</i>	1. GREENLAM
	2. DURO
	3. ARCHIDPLY
	4. EURO
	5. CENTURY
	6. ALPRO
b) <i>BWR Comm. Ply (6mm, 8mm, 12mm)</i>	1. GREENLAM
	2. DURO
	3. ARCHIDPLY
	4. EURO
	5. CENTURY
	6. ALPRO
6. <i>Laminate IS 2046 Certified</i>	1. GREENLAM
	2. SUNMICA
	3. CENTURY
	4. FORMICA
	5. ARCHIDPLY
	6. AMULYA
7. <i>HARDWARE</i>	
<i>Floor Springs</i>	1. EVERITE
	2. DOORKING
	3. SANDHU
<i>Hinges</i>	1. EARL BIHARI
	2. KAIF
<i>Drawer slides.</i>	1. EARL BIHARI
	2. KAIF
	3. FLY RAIL
<i>Mortice lock with handles, Tubular Latch with Key</i>	1. DOORSET
	2. GODREJ
	3. EQUALENT
<i>Key board Tray / CPU Trolley</i>	1. EBCL
	2. GODREJ

- |   |  |
|---|--|
| 8. <i>Adhesive IS -4835 - 1979 Certified For wood</i> | 3. HORIZON                                   |
| <i>For Foam</i>                                       | 1. FEVICOL<br>2. SPEEDEX<br>3. ARALDITE      |
| 9. <i>Plaster Of Paris</i>                            | 1. DUNLOP<br>2. CENTURY SR                   |
| 10. <i>Plastic Emulsion</i>                           | 1. SUPERFINE OR Equivalent                   |
| 11. <i>Synthetic Enamel Paint</i>                     | 1. ASIAN PAINTS<br>2. DULUX                  |
| 12. <i>Melamine</i>                                   | 1. DULUX<br>2. BERGER                        |
| 13. <i>Electrical Wiring</i>                          | 1. ASIAN PAINTS<br>2. SHALIMAR               |
| 14. Telephone wires                                   | 1. KALINGA<br>2. HAVEL'S                     |
| 15. <i>Conduits</i>                                   | 1. DELTON<br>2. FINOLEX.                     |
| 16. <i>Switches / Sockets</i>                         | 1. KALINGA<br>2. PRECISION<br>3. AKG         |
| 17. <i>Light Fixture</i>                              | 1. ANCHOR<br>2. NORTHWEST<br>3. M.K.         |
| 18. <i>Fan &amp; Exhaust fans</i>                     | 1. WIPRO<br>2. PHILLIPS                      |
| 19. <i>MCB, D.B, ELCB, MCCB's</i>                     | 1. CROMPTON GREAVES<br>2. G.E.<br>3. HAVELLS |
|   | 1. MDS<br>2. HAVELLS<br>3. INDO ASIAN        |

**NOTES: -**

All materials shall be used only after quality check / inspection / approval by architect

**PREAMBLE:-**

TO BE READ ALONG WITH DRAWINGS.

1. RATES TO BE QUOTED BOTH IN FIGURES AND WORDS.
2. ALL PAGES TO BE SIGNED AND STAMPED BY THE TENDERER.
3. THE RATE OF THE ITEMS SHALL BE APPLICABLE FOR ANY FLOOR LEVEL/ ANY NUMBER OF FLOORS, OR ANY QUANTITY.
4. THE SPECIFICATION OF THE ITEMS SHALL BE AS PER LATEST INDIAN STANDARD CODES UNLESS OTHERWISE SPECIFIED.
5. ALL MATERIALS SHALL BE AS PER APPROVED LIST AND SHOULD BE OF 1st QUALITY UNLESS OTHERWISE SPECIFIED.
6. THE RATES ARE INCLUSIVE OF ALL DUTIES AND TAXES OF ALL GOVERNMENT, MUNICIPAL OR ANY OTHER STATUTORY BODY APPLICABLE FROM TIME TO TIME.
7. RATES SHALL BE FOR ITEMS COMPLETE IN ALL RESPECTS AS PER DRAWING, INSTRUCTIONS AND APPROVAL OF THE ARCHITECT.
8. THE QUANTITIES ARE APPROXIMATE AND TENTATIVE WHICH MAY VARY DURING COURSE OF EXECUTION. THE RATES QUOTED AGAINST PARTICULAR ITEM SHALL NOT BE CHANGED WITH VARIATION IN QUANTITIES.
9. MAKING OF ANY CUTOUT / OPENING FOR ELECTRICAL / AIR – CONDITIONING WIRING / FITTING IN ANY OF THE ITEM OF FALSE CEILING, PARTITIONS, PANELING MASONRY WORK ETC. AND FINISHING EDGES JAMBS / CILLS / SOFFITS OF THE OPENING SHALL NOT BE PAID EXTRA.
10. THE TENDERER SHALL VISIT THE SITE AND SHALL SATISFY HIMSELF AS TO CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED. HE SHALL ALSO CHECK, ASCERTAIN THE LOCATIONS OF ANY EXISTING STRUCTURES OR EQUIPMENT OR ANY OTHER SITUATION WHICH MAY AFFECT THE WORK. NO EXTRA CLAIM AS A CONSEQUENCE OF IGNORANCE OR ON GROUND OF INSUFFICIENT DESCRIPTION WILL BE ALLOWED AT A LATER DATE.
11. THE QUOTED PRICE FOR ITEMS SHALL INCLUDE ALL ACCESSORIES, CONSUMMABLES ETC. AS REQUIRED TO MAKE THE ITEM COMPLETE IN ALL RESPECTS, COMPATIBLE WITH OTHER RELATED / ASSOCIATED ITEMS AND FULLY FUNCTIONAL.
12. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY ERROR, DIFFICULTY IN EXECUTION / DAMAGES INCURRED OWING TO DISCREPANCY IN DRAWINGS WHICH HAS BEEN OVERLOOKED BY HIM AND HAS NOT BEEN BROUGHT TO THE NOTICE OF THE ARCHITECT.
13. THERE IS NUMBER OF ITEMS GIVEN IN THE TENDER WHERE IN BASIC RATES INCLUDING ALL TAXES EXPECTED HAS BEEN MENTIONED IN THE TENDER. THESE ITEMS SHALL BE PURCHASED BY THE CONTRACTOR FROM THE MARKET ONLY AFTER THE APPROVAL OF QUALITY AND RATES BY THE ARCHITECT.
14. ALL HIDDEN SURFACES OF BOARD / PLY / WOOD WORK TO BE PAINTED WITH ANTI BACTERIAL PAINT FROM NAV AIR INTERNATIONAL FR 881 (VIPER) (WHITE COLOUR AS PER MANUFACTURER'S SPECIFICATIONS ON WOOD / BOARD).
15. CONTRACTOR SHALL APPOINT TECHNICALLY QUALIFIED FULL TIME SITE SUPERVISOR TO MONITORING THE DAY TO DAY PROGRESS OF WORK AT SITE ON THEIR OWN COST.

**GRAND SUMMARY**

**THE RATES ARE INCLUSIVE OF ALL DUTIES AND TAXES OF ALL GOVERNMENT, MUNICIPAL OR ANY OTHER STATUTORY BODY APPLICABLE FROM TIME TO TIME.**

<b>SL.NO.</b>	<b>SUBHEAD</b>	<b>AMOUNT (Rs.)</b>
1.0	BRANCH FURNISHING WORK (Manager Cabin only)	: Rs.
2.0	ATM FURNISHING WORK	: Rs.
		=====
	DISCOUNT (if any) %	: Rs.
		=====
	<b>TOTAL</b>	: <b>Rs.</b>
		=====

**(RUPEES** \_\_\_\_\_

**Only)**

**SIGNATURE OF CONTRACTOR**

Sl.No.	Item Description	Unit	Qty	Rate	Amount
<b>A. FURNISHING WORK (Manager Cabin only)</b>					
1.0	Dismantling / Demolishing removing existing counter's, tables, partitions, false ceiling, electrical fitting and fixture, brick work , wall / floor tiles toilet fittings & fixtures etc. to accommodate the proposed new layout and disposal of unserviceable material to a place permitted by the municipal authorities including making good any damages complete. No unserviceable dismantled material will be allowed to be accumulated at site. Decision of the architect / employer as to what constitute unserviceable material will be final and binding. The amount should include cost for carrying out any other unforeseen items required for the proper execution of the work. All complete as per approval and instructions of the Architect/ employer.	L.S.	01		
2.0	Repairing the existing false ceiling to match with the new false ceiling. Changing the ceiling level if any to make the surface flat, removing existing light fixture, etc. and cutout shall be closed with gypsum board screw fixed to ceiling section with specification matching to existing. All tapered and square edges of the existing / new boards are to be jointed and finished with jointing compound and fiber tape suitable for Gypsum board.  A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish.  A coat of primer shall be applied to be followed by a 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make.  Rectifying all defects, and cracks formed during the construction period before handing over the work complete. All complete as per approval of the architect / employer.  Note -: Horizontal surface shall be measured for the purpose of payment.	Sq.ft.	20		
3.0	Providing and fixing in position full height partition having overall thickness of 3" approx. made out of vertical and horizontal frame work of 2 ½" x 2½" Pinewood member (Ist class) at max distance of 2'-0" approx c /c both ways.  Fixing 8mm thick commercial ply on both sides with 1.0 mm thick laminate on top in approved				

Sl.No.	Item Description	Unit	Qty	Rate	Amount
	<p>shade with groove pattern as per architect instructions. 10mm thick clear Modi float glass with etching work, ( basic rate of etching Rs. 85/-) above 3'-0" &amp; up to 7'-0" fixed with steam beech wood beading of finished size 1½" x 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. Joint shall be located strictly as shown in the drawing. All exposed woodwork to be melamine polished. All complete as per approval of the Architect.</p> <p>Note: - <b>For the purpose of payment partition shall be measured excluding the area of door / door frames up to false ceiling height.</b></p> <p>Framework shall be rigidly secured to floor, bottom of slab &amp; existing walls at 2'-0" c/c with dash fasteners.</p>	Sq.ft	160		
4.0	<p>Providing and fixing Steam Beech wood in frames of size 3"x2½" approx. in doors, and other frames in moulded wood work as per design, bit mastic paint wherever required etc. (Using best quality wood). Wood protected by melamine matte finish. Item includes hold fast wherever required. All complete as per approval and instructions of the Architect/ employer.</p>	Cu.ft	01		
4.1	<p>Providing and fixing partly glazed door D1 shutter 1½" thick approx. and sizes as per drawings having 12mm thick glass panel with frosted film of 3M make or equivalent. Door of solid core of block board construction with well matched 1st class 8 mm thick commercial ply, exterior grade with vertical grains or cross bands on both faces of shutters sealed with Steam beech wood edging slip of finished section 1 ½" x ¾" approx. on all sides and finished in 1.0mm thick laminate on both sides. Heavy-duty SS butt hinges 100 x 5.5 mm with screws. Item includes door closer, cylindrical door locks, door stopper, melamine polishing. All complete as / approval of the Architect / employer.</p>	Sq.ft	21		
5.0	<p>Removing carefully, modifying &amp; Re-fixing the existing tables with side credenza as per new layout. Item includes modification in size ,changing of laminate to match with new colour scheme, moulding, hardware etc. If required. All complete as per drawing,</p>				

Sl.No.	Item Description	Unit	Qty	Rate	Amount
	approval and instructions of the Architect / employer.	Each	01		
6.0	Removing carefully, modifying & Re-fixing the existing storage as per new layout. Item includes modification in size, changing of laminate to match with new colour scheme, moulding hardware etc. If required. All complete as per drawing, approval and instructions of the Architect / employer.	Each	01		
<b>7.0</b>	<b>ELECTRICAL WORK</b>				
7.1	Providing and laying wiring from DB to Ist point for 5 pin 6 amps light plug outlets with 3 Nos. 1.5 Sq.mm copper conductor PVC insulated 1100V grade wire in concealed M.S. conduits of 25mm dia. of 16 SWG well thickness in false ceiling /wall / floor as directed including 3x2.5 sq.mm PVC insulated 1100V grade circuit wiring complete as required. Item includes outlet box, 6amp modular type switch / socket with matching plates (inner+outer) of approved colour and shade.				
a)	Primary point	Nos.	02		
b)	Looped point	Nos.	02		
7.2	Providing and fixing bracket fan including wiring for bracket fan points with 2 No. of 1.5 sq.m. PVC insulated stranded copper conductor wires& 1.00 Sq.mm PVC insulated copper wire as earth wire in concealed or exposed PVC conduits of 25mm dia. of 2mm well thickness as directed including earthing complete as required.	No.	01		
7.3	Providing and laying wiring for 5 pin 6 amps light plug outlets with 2 Nos. 1.5 Sq.mm copper conductor PVC insulated 650V grade wire in concealed PVC conduits of 25mm dia. of 2mm well thickness in false ceiling /wall / floor as directed including 1.00 Sq.mm PVC insulated copper wire as earth wire complete as required. Item includes outlet box, 5amp modular type switch / socket with matching plate of approved colour and shade.				
		Nos.	02		
7.4	Wiring for 15 amps power outlet points with 2 No. 4.0 sq.mm PVC insulated stranded copper conductor wire for the first power outlet and 1 nos. of 2.5 sq.mm PVC insulated copper conductor wire for the second outlet, 1 no. of 1.5 sq.mm. as earth wire in concealed PVC conduits in false ceiling /wall /ceiling as directed including earthing the third pin				

Sl.No.	Item Description	Unit	Qty	Rate	Amount
	complete including chrome plated outlet boxes, 1 no. Switch (push button) and 1 no. Socket of 15amp. 5 pin (modular type) with matching plate of approved shade as required. (Two power outlets shall be connected on each circuit)	Set	02		
7.5	Wiring for 3 pin AC metal clad point with 2 no. of 6 sq.mm & 1 no.2.5 Sq.mm PVC insulated copper wire as earth wire Copper wire in PVC conduit 25mm dia. of 2mm well thickness with 20amp socket controlled by 32 amp SP MCB.	No.	01		
7.6	Providing and fixing PVC box of 72 mm x 208 mm x 60 mm deep (nominal size) on surface or in recess with 3 sockets controlled by 1 No. 6 A switch including making connections (For UPS point only)	Nos.	02		
	<b>FIXTURE &amp; FITINGS</b>				
8.0	Supply, delivery at site, receiving, storing, handling, cartage at site, assembling, erection including the down rods as required at site, connecting, testing and commissioning of the following Ceiling mounted reflector type Compact Fluorescent light fixtures, including the lamps. Rates shall include all taxes and duties, transportation etc. complete.				
8.1	4x14 FTL T5 BAJAJ BMTRA 414 V2 & matching to existing fittings.	Nos.	02		
8.2	Downlighter BJDR 118 H WEB ( BAJAJ Make)& matching to existing fittings.	Nos.	02		
8.3	1x50 watts halogen light as per BAJAJ Cat No: BLDR50 DH SL	Nos.	02		
8.4	Removing & Re-fixing of Wall Fan at new location complete including wiring from the socket to fan complete.	No.	01		
8.5	Supplying & fixing call bell buzzer with indicator & reset facility operating on 230 volts (wiring is counted as light point).	No.	01		
<b>9.0</b>	<b>SUBMAIN WIRING</b>				
9.1	Sub Mains wiring including cost of PVC Conduit				
(a)	4x16 sq.mm + 1x2.5 sq.mm Cu wire (for AC DB)	Mtr.	05		
(b)	4x10 sq.mm + 1x4 sq.mm Cu. Wire (for UPS Supply)	Mtr.	05		

Sl.No.	Item Description	Unit	Qty	Rate	Amount
<b>10.0 TELEPHONE SYSTEM</b>					
10.1	Wiring for telephone points with 2 pair 4/5 pair .51mm dia ATC (annealed tinned Cu wire) with PVC insulated PVC sheathed telephone cable from tag block to the point including providing ferrules at both ends and termination at both ends including providing & fixing RJ 11 outlet, faceplate and mounting box complete of modular type (where 2 such points are shown, 2 such wires shall be provided) This work includes providing PVC conduits in chases from the raceway to the point.	Nos.	02		
<b>11.0 COMPUTER NETWORKING</b>					
11.1	Wiring for computer networking from I/O hub to computer workstation with Cat -5e computer cable including providing ferrules at both ends and termination at both ends including providing & fixing frame for Cat 5 with shutter, RJ 45 outlet, faceplate and mounting box complete of modular type, This work includes providing PVC conduits in chases from the I/O hub to the point.	Nos.	02		
11.2	Supplying and fixing Patch Cord-1 Meter-(DBPS Mounting Cord, 7ft.).	Nos.	02		
<b>12.0 AIR-CONDITIONING WORK</b>					
12.1	Removing carefully the existing A.C'S (1.5 / 2.0TR) complete including indoor, outdoor unit (if required), MS brackets, copper piping & stabilizers etc. & fixing as per new layout. All complete as per approval of the architect/ employer.	Each	01		
b)	Providing and filling the gas in existing air conditioning machine complete in all respect as per approval of architect/ employer.	Each	01		
12.2	Providing fixing and testing of copper refrigerant piping of sizes 1/2" / 1/4" dia for 1.5 TR split duly insulated with nitrile rubber insulation of 9mm thickness with interconnecting cabling.	R.mtr.	10		
12.3	Providing and fixing drain piping up to 40 mm dia with all accessories e.g. elbows, unions, sockets, reducers, reducing tees, nipples etc. Complete job including cutting chiseling in walls, floor and making good of all chases/cuts etc. and discharging the drain into a floor trap/ gully as per site conditions.	R.mtr.	10		
<b>1.0 FURNISHING WORK TOTAL :</b>					

Sl.No.	Item Description	Unit	Qty	Rate	Amount
--------	------------------	------	-----	------	--------

**B. ATM FURNISHING WORK**

1. Providing and fixing suspended false ceiling in Glass Fiber Reinforced Gypsum board. Gypsum board suspended ceiling shall comprise of providing and fixing G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam to the required curvature with nylon sleeves and screws at not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners. Ceiling section (MF-5) of 0.50mm thickness having knurled web of 51.5mm and two flanges of 25.6mm each with lips of 10.5mm bent to the required profile by cutting both its flanges. Suitable bracing to be provided wherever the flanges are cut with 0.50mm flats. Steel screws, are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Glass Fiber Reinforced Gypsum board (conforming to IS-2095-1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres.

Screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied.

Sl.No.	Item Description	Unit	Qty	Rate	Amount
	Rectifying all defects and cracks formed during the construction period before handing over the work complete. The rates shall include for necessary supports, scaffolding and labor. All as per drawing, approval and instructions of the architect / employer.	Sq.ft	105		
2	Providing and fixing in position paneling on existing wall of having frame work of Hardwood sections of size 2" x 3/4" approx. at max. distance of 2'-0" approx. c/c both ways. Fixing 6mm commercial ply on to the framework and finishing with 1.0mm thick laminate of approved shade and pattern including making grooves etc. complete.  All as per drawing and approval of the Architect / employer.	Sq.ft	365		
3.	Providing and fixing 7" x 6" vertical boxing made of 19mm thick P.F. board finished with 1.0mm thick laminate of approved shade.	R.ft	10		
4.	Providing and fixing Fully glazed aluminum door including door frame/ chowkhat. 4"x 2" Aluminium frame of 16 gauge and 22-25 micron electro colour anodizing. A panel of one piece 12mm thick float glass with antishatter film and weather strip insulation on the shutter edges, 1" dia. 1'-6" long SS brushed finish handle on both sides including heavy duty double action ISI marked floor-spring with steel cover plate, with edges rounded, all accessories etc. Cost includes cutting and making good the floors for fixing floor spring. All complete as per approval and instructions of the Architect / employer.	Sq. ft.	21		
5.	Providing and fixing aluminium glazing as per following specification:-  Aluminium windows of 14 gauge and 22-25 micron electro colour anodizing of approved shade. Vertical and horizontal members of hollow sections no. WS 1468 Hindalco or equivalent along with beading of WS 1467. 6mm thick clear float glass. All complete including rubber gaskets, screws, cleats etc. erected at site and in position. Item includes cutting and repair to damaged brick work / concrete work with cement plaster 1: 4 (1 cement: 4 coarse sand), scaffolding, shuttering etc. All complete as per approval and instructions of the Architect / employer.	Sq.ft	28		

Sl.No.	Item Description	Unit	Qty	Rate	Amount
6.	Supply, installation, testing and commissioning of recessed / surface mounted type 6WAY SPN double door distribution boards consisting of a) 63 amp. DP RCBO, 300 Ma, 10 KA as incomer b) 3 nos. 20ASP MCB'S c) 1 NO. 10 A SP MCB'S d) 1 NO. 10 A digital weekly programmable timer switch similar to MDS REX 2000.	Each	01		
7.	Supply, installation, testing of 63 A DP MCB IN 16 gauge MS powder coated enclosures with accessories.	Each	01		
8.	Wiring for 20A 3pin modular plate type socket outlet with switch socket from DB in 25mm dia rigid PVC conduit embedded in wall surface with 3 x 2.5sq.mm copper wire.	Each	02		
9.	Wiring for the following light points with specification same as <b>item no. 7.1 Furnishing work 'A'</b> .				
a)	Primary point	Nos.	02		
b)	Looped point	Nos.	01		
10.	Wiring for UPS power socket with specification same as <b>item no. 7.6 Furnishing work 'A'</b> .	Nos.	02		
11.	Wiring for telephone points with specification same as <b>item no. 11.1 Furnishing work 'A'</b> .	Nos.	02		
12.	Providing and fixing 40mm PVC conduit of ISI make saddling complete for connectivity from dish antennae on the roof top to the ATM.	R.mtr.	30		
13.	Supplying, installation and commissioning of automatic 24HRS. programmable TIMER of required capacity to run A.C. alternately <b>(MDS/L&amp;T/Other reputed make)</b> .	Each	01		
14.	Wiring for 3 pin AC metal clad point with specification same as <b>item no. 7.5 Furnishing work 'A'</b> .	Each	02		
15.	S/T/C of the following Compact Fluorescent light fixtures with specification same as <b>item no. 8 Furnishing work 'A'</b> .				
a)	18 W LED SQ Downlighter as per cat. PCGLD 18W, POLYCAB.	Nos.	02		
b)	14 W LED round Downlighter as per cat. PCGLDL X 14WR, POLYCAB.	Nos.	02		
16.	Providing earth station comprising of 300x300x3mm copper plate with earthing resistance less 2ohms including watering PVC/GI pipe with funnel excavation back filling salt and coal filling in layers 10" x10" masonry chambers with sand plaster, RCC cast iron lid,				

Sl.No.	Item Description	Unit	Qty	Rate	Amount
	earthing connectivity to be in 10 swg copper wire in PVC conduit from bottom of pit to the existing ground level complete.	Each	01		
17.	Earthing of UPS with 1C- 4sq.mm copper in 25mm PVC conduit with accessories, lugs etc.	R.mtr.	10		
18.	Sub Mains wiring including cost of PVC Conduit				
(a)	4x10 sq.mm + 1x4 sq.mm Cu. Wire (for UPS Supply)	Mtr.	25		
19.	Earthing of UPS with 1C- 4sq.mm copper in 25mm PVC conduit with accessories, lugs etc.	Each	01		
<b>1.0</b>	<b>ATM FURNISHING TOTAL</b>				<b>:</b>